Annex to declaration of accreditation (scope of accreditation)

Normative document: EN ISO/IEC 17025:2017

Registration number: K 149

of TPF Control B.V.

This annex is valid from: 17-03-2022 to 01-12-2025 Replaces annex dated: 21-01-2022

Location(s) where activities are performed under accreditation

Head Office

Van Heemstraweg 19 6657 KD Boven-Leeuwen The Netherlands

Location	Abbreviation/ location code	
Van Heemstraweg 19 6657 KD Boven-Leeuwen The Netherlands	BL	
On site at the customer	CU	

HCS code	Measured quantity, Instrument, Measure	Range	CMC ¹	Remarks	Location
FG 1 0	FLOW OF GAS				
FG 1 0	Gas flow rate	0.5 ml/min – 5 ml/min	0.60 %		BL
		5 ml/min – 100 l/min	0.18 %		
		0.5 m ³ /h – 2500 m ³ /h	0.25 %		
FG 1 0	Gas flow rate	5 ml/min – 50 l/min	0.27 %		CU
		0.8 m ³ /h – 1000 m ³ /h	0.35 %		

¹ Calibration and Measurement Capability (CMC): Demonstrated measurement uncertainty, with coverage probability of 95%, in a given measurement point or measurement range. Measurement uncertainty, *U*, is calculated according to EA-4/02 "*Evaluation* of the Uncertainty of Measurement in Calibration".

This annex has been approved by the Board of the Dutch Accreditation Council, on its behalf,

J.A.W.M. de Haas

Dutch Accreditation Council RvA Page 1 of 2

Annex to declaration of accreditation (scope of accreditation)

Normative document: EN ISO/IEC 17025:2017

Registration number: K 149

of TPF Control B.V.

This annex is valid from: 17-03-2022 to 01-12-2025 Replaces annex dated: 21-01-2022

HCS code	Measured quantity, Instrument, Measure	Range	CMC ¹	Remarks	Location
FG 1 1	Gas mass flow rate	0.5 ml _n /min – 5 ml _n /min	0.60 %		BL
		5 ml _n /min— 50 l _n /min	0.18 %		
		0.5 m ³ _n /h – 2500 m ³ _n /h	0.25 %		
FG 1 1	Gas mass flow rate	5 ml _n /min – 100 l _n /min	0.15 %	Viscous seal piston provers	BL
FG 1 1	Gas mass flow rate	5 ml _n /min – 50 l _n /min	0.27 %		CU
		3 m ³ _n /h – 1000 m ³ _n /h	0.35 %		
TE 0 0	TEMPERATURE				
TE 4 0	Self-indicating thermometers	-80 °C – -40 °C	0.1 °C	Using dry block furnace	BL
		140 °C – 400 °C	0.2 °C	Using dry block furnace	
		-40 °C – 140 °C	0.015 °C	Using oil bath	
		0 °C – 50 °C	0.2 °C	In air	
RH 0 0	HUMIDITY				
RH 1 0	Hygrometers	10 %rh – 95 %rh	1.7 %rh	20 °C – 55 °C	BL
PV 0 0	PRESSURE AND VACUUM				
PV 1 0	GAS PRESSURE				
PV 1 1	Absolute pressure	0.2 kPa – 1000 kPa	0.7·10 ⁻³ · <i>p</i> + 25 Pa		BL
PV 1 1	Absolute pressure	50 – 115 kPa	1.7·10 ⁻⁴ · <i>p</i>		BL
PV 1 2	Gauge pressure	-95 kPa – 1000 kPa	0.7⋅10 ⁻³ ⋅ <i>p</i> _e + 25 Pa		BL

Remarks:

- Calibration and Measurement Capability (CMC): Demonstrated measurement uncertainty, with coverage probability of 95 %, in a given measurement point or measurement range
- Measurement uncertainty, U, is calculated according to EA-4/02 "Evaluation of the Uncertainty of Measurement in Calibration".
- The flow units ml_n/min and m³_n/h refer to gases under normal (n) conditions of 1013.25 mbar and 0 °C.
- The flow units ml/min and m³/h refer to gases under actual (flowing or line) conditions.
- Fixed normal densities on [kg/m³] are used to convert from the flow unit [ln/min] to the mass flow unit [g/h].

• Densities according to NEN-EN-ISO 6976:-2016.

Dutch Accreditation Council RvA Page 2 of 2